BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41737

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Name of Work:Drilling of Borewell and Providing Pipeline in ward No 11 Kuvempunagara Vidyaranyapura sub division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B Chandrashekar ( )	
				In Figures	In Words
1	4	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its quality & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work	Each BW	3428.88	Rupees Three Thousand Four Hundred Twenty Eight and Eighty Eight Paise Only
2	200	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars and cap etc.,) ,with all lead and lift, loading, unloading and labour charges etc., complete and as per the directions of the Engineer-in-charge of the work 0 to 50 m	Rmtr	315.77	Rupees Three Hundred Fifteen and Seventy Seven Paise Only
3	200	50 to 100 m	Rmtr	402.22	Rupees Four Hundred Two and Twenty Two Paise Only
4	200	100 to 150 m	Rmtr	414.96	Rupees Four Hundred Fourteen and Ninety Six Paise Only
5	200	150 to 200 m	Rmtr	487.76	Rupees Four Hundred Eighty Seven and Seventy Six Paise Only
6	200	200 to 250 m	Rmtr	576.94	Rupees Five Hundred Seventy Six and Ninety Four Paise Only
7	200	250 to 300 m	Rmtr	637.0	Rupees Six Hundred Thirty Seven Only
8	200	300 to 350 m	Rmtr	750.75	Rupees Seven Hundred Fifty and Seventy Five Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender R... B Chandrashe... (	
				In Figures	In Words
9	320	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by baseic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985, one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and durties) Prices include Collar-medium duty	Rmtr	1255.8	Rupees One Thousand Two Hundred Fifty Five and Eighty Paise Only
10	72	Providing 250mm dia PVC Pipe 6kg/cm etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	1001.0	Rupees One Thousand One Only
11	4	Providing and fixing Borewell Cap & Clamp Set etc., complete and as per the directions of the Engineer-in-charge of the work	Set	1638.0	Rupees One Thousand Six Hundred Thirty Eight Only
12	4	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps etc., complete and as per the directions of the Engineer-in-charge of the work	No	57783.18	Rupees Fifty Seven Thousand Seven Hundred Eighty Three and Eighteen Paise Only
13	1400	GI Pipe 50 mm'B' class etc., complete and as per the directions of the Engineer-in-charge of the work	m	377.65	Rupees Three Hundred Seventy Seven and Sixty Five Paise Only
14	236	Heavy Duty Collar 50 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	163.8	Rupees One Hundred Sixty Three and Eighty Paise Only
15	4	Providing non-return valve 50 mm etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	1638.0	Rupees One Thousand Six Hundred Thirty Eight Only
16	72	Providing Gate Valve 50 mm etc., complete and as per the directions of the Engineer-in-charge of the work	Nos	1638.0	Rupees One Thousand Six Hundred Thirty Eight Only
17	4	Supplying and Fixing Out Door Panel up to 15 HP etc., complete and as per the directions of the Engineer-in-charge of the work	No.	14105.0	Rupees Fourteen Thousand One Hundred Five Only
18	2560	Submersible Cable 1x3x6.0 Sq.mm etc., complete and as per the directions of the Engineer-in-charge of the work	M	131.04	Rupees One Hundred Thirty One and Four Paise Only
19	216	Labour charges for erection as new /repaired submercible pumpset allong with GI pipe (32/50mm) cable (new submercible pumpset if required will be supplied by the department free of cost and released pumpset shoud be handed over to department including transportation (Each lenth =6.00) etc., complete and as per the directions of the Engineer-in-charge of the work	L	80.08	Rupees Eighty and Eight Paise Only
20	4	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., complete and as per the directions of the Engineer-in-charge of the work	Each	265.72	Rupees Two Hundred Sixty Five and Seventy Two Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B Chandrashekar ( )	
				In Figures	In Words
21	140	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A 4 core 16 Sqmm etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	136.5	Rupees One Hundred Thirty Six and Fifty Paise Only
22	140	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	10.81	Rupees Ten and Eighty One Paise Only
23	120	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	69.16	Rupees Sixty Nine and Sixteen Paise Only
24	16	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV etc., complete and as per the directions of the Engineer-in-charge of the work	Mtr	304.85	Rupees Three Hundred Four and Eighty Five Paise Only
25	4	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	245.7	Rupees Two Hundred Forty Five and Seventy Paise Only
26	4	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia etc., complete and as per the directions of the Engineer-in-charge of the work	No	2729.73	Rupees Two Thousand Seven Hundred Twenty Nine and Seventy Three Paise Only
27	24	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete and as per the directions of the Engineer-in-charge of the work	No.	158.34	Rupees One Hundred Fifty Eight and Thirty Four Paise Only
28	4	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 5-32Amps Group A TPN etc., complete and as per the directions of the Engineer-in-charge of the work	No	1560.65	Rupees One Thousand Five Hundred Sixty and Sixty Five Paise Only
29	93600	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete and as per the directions of the Engineer-in-charge of the work	Sq.Cm	0.32	and Thirty Two Paise Only
30	97.2	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strata by Manual Means etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	238.42	Rupees Two Hundred Thirty Eight and Forty Two Paise Only
31	270	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation etc., complete and as per the directions of the Engineer-in-charge of the work	Rmtr	188.37	Rupees One Hundred Eighty Eight and Thirty Seven Paise Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Ra B Chandrashe (	
				In Figures	In Words
32	32.04	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including watering, consolidation in layers of 15 cm thick including disposing of the sunplus earth with a lead of 200 mtrs	Cum	2931.42	Rupees Two Thousand Nine Hundred Thirty One and Forty Two Paise Only
33	65.16	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including watering, consolidation in layers of 15 cm thick including disposing of the sunplus earth with a lead of 200 mtrs etc., complete and as per the directions of the Engineer-in-charge of the work	Cum	93.73	Rupees Ninety Three and Seventy Three Paise Only

Signature of the Contractor

Executive Engineer 22/06
Byarayanapura Division
BBMP, Bangalore - 92

22/06